







Pre-Task	<ul style="list-style-type: none"> • Consider the task and follow safe job procedures, industry best practices, and legislative requirements. • Complete a hazard assessment and follow the controls. Watch for uneven surfaces when installing signs. • Be familiar with the Traffic Accommodation Strategy and traffic control plan. • Follow the road authority’s contract document and specifications. • Ensure the use of all PPE. This includes gloves, safety glasses and high visibility apparel.
During	<ul style="list-style-type: none"> • Ensure the signage is in good condition, clean, and within the motorist’s light of vision. • Use the traffic control plan to determine specific sign placement and distances. • Ensure sign is secure and will not be knocked over or blown over by the wind. • Cover or remove unneeded signs for periods of inactivity or when the hazards are no longer present. • Inspect signs as per contract specification or employer policy on a regular basis.
Post-task	<ul style="list-style-type: none"> • Remove all signs when the job is completed. • Secure all signs in a clean location when job is completed.

Task/Environment/Equipment	
Traffic Control Signage	
Protective Measures	
SSHA	
Engineering	
Training	
SJP	
ERP	
PPE	

The information presented in this publication is intended for general use and may not apply to every circumstance. It is not a definitive guide to OHS legislation or industry standards. This does not relieve persons using this publication from their responsibilities under applicable legislation. The Alberta Construction Safety Association does not guarantee the accuracy of, nor assume liability for, the information presented here.

Icons from The Noun Project: *warning-clipboard* by Suncheli Project, *secure* by Markus, *training* by Musmellow, *checklist* by Vectors Market, *agenda* by Rflor, *safety glasses* by André Renault